



CENTRALIZED FURNITURE AND ITS IMPACT ON IT




MCA/BRAC IS Procurement

- 1391- TAB A (USACE Managed):
 - Building (Brick, Mortar, Building Systems)
 - Real Property for IS Infrastructure (MH & Duct, OSP Cabling, ISP Cabling from Wall Jack Outlets to Telecom Room)
- 1391- TAB F (ISEC Managed):
 - Telephone, Data & TACLANE Switches, Phones, DDM 2000 SONET Termination Component
- User Proponent (DOIM Managed):
 - NIC Cards, Computers, Servers, Printers & VTC




MODULAR FURNITURE IS CONSIDERATIONS

- Ensure AE design & construction specifications to include ISP connectivity to cross-connects in the wall/column
- Ensure IS connectivity complies with I3A Design Guide
- Ensure ISP runs from Telecommunications Room to the Modular Furniture receptacle is less than 295 LF



MODULAR FURNITURE IS CONSIDERATIONS

- Design Classified Area requirements to meet Army Security Requirements
- Spanning the IS connectivity gap from column/wall cross-connect to the modular furniture IS receptacles



RECOMMENDATIONS

- Include the ISEC/DOIM in the Proposal, Design & Construction QA Reviews
- Contact ISEC during planning efforts to determine Implementer of SIPRNET requirements
- Coordinate with ISEC in design development for requirements above the SIPRNET level